



H12-425^{Q&As}

HCIP-Data Center Facility Deployment V2.0

Pass Huawei H12-425 Exam with 100% Guarantee

Free Download Real Questions & Answers **PDF** and **VCE** file from:

<https://www.pass4itsure.com/h12-425.html>

100% Passing Guarantee
100% Money Back Assurance

Following Questions and Answers are all new published by Huawei
Official Exam Center

-  **Instant Download** After Purchase
-  **100% Money Back** Guarantee
-  **365 Days** Free Update
-  **800,000+** Satisfied Customers





QUESTION 1

Where is the recommended installation location for the Smart ETH socket?

- A. Control skylight
- B. Inside the network cabinet
- C. Inside the threshold
- D. Side of the cable trough on the top of the cabinet

Correct Answer: D

QUESTION 2

Draining impurities from the refrigerant pipe should: (Choose 3)

- A. Block one of the pipe ports.
- B. Fill the pipe with high-pressure nitrogen.
- C. Quickly remove the pipe plug and avoid facing people to prevent injury.
- D. To discharge nitrogen from the outdoor unit

Correct Answer: ABC

QUESTION 3

A certain distance should be reserved at the rear and top of the UPS5000-E, ensuring ventilation and heat dissipation.

- A. TRUE
- B. FALSE

Correct Answer: A

QUESTION 4

When the battery is out of control, what is the main cause of deformation and bulging due to the internal pressure becomes larger?

- A. Electrolyte leakage
- B. More electrolyte



C. Gas precipitation

D. Plate gasification

Correct Answer: C

QUESTION 5

After all the NetEco monitoring cables are connected, users need to check (). (Choose all apply)

A. Power cables and signal cables are bound separately.

B. Proper redundancy is reserved at connectors of signal cables.

C. Signal cable connectors are intact.

D. Proper redundancy is reserved at the turning point for signal cables.

Correct Answer: ABCD

QUESTION 6

NetCol5000-A25 kW indoor unit needs neutral wires.

A. TRUE

B. FALSE

Correct Answer: A

QUESTION 7

For NetCol5000-A installation, the required time of preserving positive pressure is () hours.

A. 8

B. 12

C. 24

D. 16

Correct Answer: C

QUESTION 8

To shut down one UPS in UPS2000-G-20kVA parallel system, you must ().



- A. Perform "shut down operation" on the UPS twice.
- B. Perform "shut down operation" on the UPS only once
- C. Turn off the input circuit breaker of the UPS
- D. Perform "shut down operation" on all UPS

Correct Answer: A

QUESTION 9

Before battery installation, the open circuit of full capacity should be check.

- A. TRUE
- B. FALSE

Correct Answer: A

QUESTION 10

If IP21 components is configured, the top air outlet kits can also be installed on the UPS5000-E.

- A. TRUE
- B. FALSE

Correct Answer: B

QUESTION 11

The compressor of NetCol5000-A generates a loud noise, possible reasons (). (Choose 3)

- A. Liquid refrigerant is returning to the compressor.
- B. The lubricant is insufficient
- C. The sheet metal for securing the compressor during transportation are not
- D. The phase sequence of power supply may be incorrect

Correct Answer: ABC

QUESTION 12



In direct ventilation mode, the direct ventilation system exchanges heat between outdoor cool air and indoor hot air.

- A. TRUE
- B. FALSE

Correct Answer: A

QUESTION 13

Power segment function is enabled on UPS2000-G-20kVA. Which will cause the loads connected with PL terminals power- off? (Choose 2)

- A. Overload
- B. Battery under voltage
- C. Mains input interruption
- D. Mains Under voltage

Correct Answer: AB

QUESTION 14

For NetCol5000-A installation, preserving positive pressure for the pipes is the same as preserving negative pressure. You can select either to hold.

- A. TRUE
- B. FALSE

Correct Answer: B

QUESTION 15

Which component does not support wireless networking?

- A. Access actuator
- B. AC Actuator
- C. ETH converter
- D. XXX

Correct Answer: C



VCE & PDF

Pass4itSure.com

<https://www.pass4itsure.com/h12-425.html>

2024 Latest pass4itsure H12-425 PDF and VCE dumps Download

[H12-425 Practice Test](#)

[H12-425 Study Guide](#)

[H12-425 Exam Questions](#)